The Laser MegaJoule Facility Status Report

Irwin ISSURY, Jean-Philippe AIRIAU, Yves TRANQUILLE-MARQUES





- 22 bundles of 8 beams
- 4 laser bays: 3 bays with 5 bundles + 1 bay with 7 bundles
- **1 PetaWatt laser line** : a high energy multi-Petawatt laser beam with 500 fs to 10 ps short pulse and a few kJ compressed energy

By the end of 2023:

Expected laser bundle

• 1 PETAL laser beam fully operational

Expected diagnostic

- 15 LMJ bundles fully operational
- 2 new bundles assembled
- 20 Target Diagnostics operational
- 2 new diagnostics under construction
- Target shot with 10 bundles and 12 TD

next 2 year the n (2025):

- Full completion of the 22 bundles
- Commissioning of 4 Target more Diagnostics
- 6th Arrival of a equatorial SID

Target Diagnostics

4 into main



Main software evolutions

(2024)

The LMJ facility has a control system which is divided into 4 layers.



SID: Telescoping system that provides a precise positioning of a target diagnostic close to the center of the target chamber

- Development of a full automated sequence for (1) final optics assembly inspection and (2) laser beam alignment during night activities without technical operators
- Upgrade of the Power Conditioning Module (PCM) in order to shutdown during combined LMJ-PETAL safety avoid experiments

Major experiments and results

Final optics preservation experiments : For a better knowledge of the final optics laser damage phenomenon on LMJ facility





Fusion experiments: 10 baser beams + 12 target diagnostics



Indirect drive experiments with symmetric irradiation



Commissariat à l'Energie Atomique et aux **Energies Alternatives (CEA)** 16 avenue des Sablières – Le BARP, FRANCE



